

Theatre: McLeod Theater			Production: Tuck Everlasting			
Date: 30-Nov-20		By: Nate Mohlman				
Unit: Foster Manor		Assist:				
Notes:		Page: 1				
Time Estimate Explanation:					Jump To:	
Wood	Hrs.	Metal	Hrs.	Load-IN	Hrs.	Main Price Sheet Build Schedule Bill of Materials Summary Sheet
Cutting	20.50	Clean	0.75	Transport		
Layout	10.50	Cutting	1.50	Finishing	2	
Assemble	30.00	Drill	2.75	Rigging		
Skin	7.00	Jig	1.00	Install		
Face	2.00	Weld	2.00	Automation		
Detail	3.50	Grind	3.50	Trouble Shoot	3	
Molding	7.50	Rig		Designer Notes	1	
Rig						
					98.50	Est. Time
					* 2.255	Contingency
					222	Total Time
					Current:	\$ 565.61
Call Name	Materials	Unit	Unit Price	Quantity	Weight	Cost
Platforms						
Maso/HB_1/4"	1/4" Hardboard; 4' x 8'	Sht.	\$14.49	3.00	67.50	43.47
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	1.00	18.00	15.98
Center Wall						
Pine 1x12x16 S	1x12x16', Select	16'	\$26.99	4.00	131.26	107.96
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	8.00	144.00	127.84
Pine 2x4x16 D	2x4x16', D Fir	16'	\$7.28	2.00	40.83	14.56
Side Walls						
Pine 1x12x16 S	1x12x16', Select	16'	\$26.99	3.00	98.45	80.97
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	4.00	72.00	63.92
Ply_3/4_CD	3/4" CDX Plywood	Sht.	\$23.99	1.00	70.40	23.99
Stl_STS_1" _16g	1" SQ Tube, 16 Gauge (.065)	20	\$18.00	2.00	33.08	36.00
Fence Gate						
Ply_3/4_CD	3/4" CDX Plywood	Sht.	\$23.99	1.00	70.40	23.99
					Total Weight (lbs):	745.92
					Sub-Total:	\$ 538.68
					Contingency:	\$ 26.93
					Total:	\$ 565.61

Theatre: McLeod Theater			Production: Tuck Everlasting			
Date: 30-Nov-20		By: Nate Mohlman				
Unit: Tuck Cottage		Assist:				
Notes:		Page: 2				
Time Estimate Explanation:				Jump To:		
Wood	Hrs.	Metal	Hrs.	Load-IN	Hrs.	Main Price Sheet Build Schedule Bill of Materials Summary Sheet
Cutting	17.75	Clean		Transport		
Layout	7.75	Cutting		Finishing	1.5	
Assemble	30.75	Drill		Rigging		
Skin		Jig		Install		
Face	5.00	Weld		Automation		
Detail	8.25	Grind		Trouble Shoot	1	
Molding	4.00	Rig		Designer Notes	2	
Rig						
					78.00	Est. Time
					* 2.255	Contingency
					176	Total Time
					Current:	\$ 689.31
Call Name	Materials	Unit	Unit Price	Quantity	Weight	Cost
Platforms						
Pine 2x4x16 D	2x4x16', D Fir	16'	\$7.28	2.00	40.83	14.56
OSB 3/4"	Oriented Strand Board, 3/4"	Sht.	\$19.99	2.00	160.00	39.98
Maso/HB_1/4"	1/4" Hardboard; 4' x 8'	Sht.	\$14.49	6.00	135.00	86.94
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	2.00	36.00	31.96
Walls						
Pine 4x4x8	4x4x8', Douglas Fir	8'	\$8.99	16.00		143.84
Pine 2x4x16 D	2x4x16', D Fir	16'	\$7.28	3.00	61.25	21.84
Ply_3/4_CD	3/4" CDX Plywood	Sht.	\$23.99	2.00	140.80	47.98
Roof						
Pine 2x4x16 D	2x4x16', D Fir	16'	\$7.28	2.00	40.83	14.56
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	4.00	72.00	63.92
Gen_Supply	General Supply	Ea.	\$50.00	2.00		100.00
Doors						
Pine 1x12x16 S	1x12x16', Select	16'	\$26.99	1.00	32.82	26.99
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	4.00	72.00	63.92
					Total Weight (lbs):	791.53
					Sub-Total:	\$ 656.49
					Contingency:	\$ 32.82
					Total:	\$ 689.31

Theatre: McLeod Theater			Production: Tuck Everlasting			
Date:	30-Nov-20		By:	Nate Mohlman		
Unit:	Fair Booths		Assist:			
Notes:	Unit includes smaller elements in the fair scene		Page:	7		
Time Estimate Explanation:			Jump To:			
Wood	Hrs.	Metal	Hrs.	Load-IN	Hrs.	Main Price Sheet Build Schedule Bill of Materials Summary Sheet
Cutting	27.00	Clean		Transport		
Layout	11.75	Cutting		Finishing	1.5	
Assemble	48.50	Drill		Rigging		
Skin		Jig		Install		
Face		Weld		Automation		
Detail	9.50	Grind		Trouble Shoot	2	
Molding		Rig		Designer Notes	2	
Rig						
					102.25	Est. Time
					* 2.255	Contingency
					231	Total Time
					Current:	\$ 422.55
Call Name	Materials	Unit	Unit Price	Quantity	Weight	Cost
Frames / Structure						
Pine 2x4x16 D	2x4x16', D Fir	16'	\$7.28	4.00	81.66	29.12
Ply_1/2_CD	1/2" CDX Plywood	Sht.	\$17.99	2.00	80.00	35.98
MDF_1/2"	1/2" MDF; 4' x 8'	Sht.	\$26.48	1.00		26.48
Fascia						
Lauan_3/16"	3/16" Lauan; 4' x 8'	Sht.	\$15.98	2.00	36.00	31.96
Muslin 59" HVY	59" HVY WT NFR Cut Price	Yd.	\$5.95	15.00	9.75	89.25
Podium						
Ply_3/4_CD	3/4" CDX Plywood	Sht.	\$23.99	2.00	140.80	47.98
Gen_Supply	General Supply	Ea.	\$50.00	1.00		50.00
Wagon						
Pine 2x4x16 D	2x4x16', D Fir	16'	\$7.28	6.00	122.50	43.68
Ply_3/4_CD	3/4" CDX Plywood	Sht.	\$23.99	2.00	140.80	47.98
					Total Weight (lbs):	611.51
					Sub-Total:	\$ 402.43
					Contingency:	\$ 20.12
					Total:	\$ 422.55

